DATE 13/11/1959 SH. 1 OF 6 COMPILED BY R.W.T.		TMC	SPE	CI	FICA	TION		NO.	<b>S</b> - 10032
	TITLE:	PRODUCTION	TEST ING	OF	System	CRTC-2	- C	DTC-1	JOB
APPROVED R.W.J							10	C	

INSTRUCTIONS FOR THE

PRODUCTION TESTING

OF THE

SYSTEM CRTC-2, CDTC-1

DATE_13/11/59 SH2_OF_6 COMPILED BY		TMC	SPECIFICATION NO. S	- 10032
R.W.T.	TITLE:	PRODUCTION	TESTING OF SYSTEM CRTC-2, CDTC-1 Join	<b></b>
APPROVED R.W.J.	•		Suc	

## INDEX

			PAGE
1.	Test equipment required		3
2.	Connection of test equipmen	nt	4
3.	Test procedure		5
	3.1 Preliminary inspection	n.	5
	3.2 Functional tests		5
	3.3 Power tests		5
	Block schematic diagram	CK-10332	
	Interconnection diagram	CK-10333	

TMC SPECIFICATION NO. S - 10032

TMC SPECIFICATION NO. S - 10032


TMC SPECIFICATION NO. S - 10032

TITLE: PRODUCTION TESTING OF SYSTEM CRTC-2, CDTC-1 JOB

APPROVED R.W.J.

1. TEST EQUIPMENT REQUIRED

- 1.1 Multi-lamp function tester.
- 1.2 Two GPT-750 Transmitters.
- 1.3 One PCA-1.
- 1.4 One 52 ohm R.F. load.
- 1.5 Interconnecting wires and cables.
- 1.6 Two XFK units.



DATE 13/11/59 SH. 5 OF 6 COMPILED BY R.W.T.		TMC	SPECI	FICAT	ION	NO.	<b>S</b> - 10032
	TITLE:	PRODUCTION	TESTING OF	F SYSTEM	CRTC-2,	CDTC-1	JOB
APPROVED RANA		· · · · · · · · · · · · · · · · · · ·				1200	1.

3. TEST PROCEDURE

- 3.1 Preliminary inspection
- 3.1.1 Inspect system for interconnection errors.
- 3.1.2 Check that all terminal screws are tight.

## 3.2 Functional tests

- 3.2.1 Switch CONTROL SELECTOR to "local" and check that the lamps corresponding to the various switch positions on CTCU-1 light in accordance with the switch positions and key position etc.

  Note that TRANSMITTER SELECTOR is inoperative with H.T. ON.
- 3.2.2 Switch CONTROL SELECTOR to REMOTE and check that the lamps light in accordance with the switch positions on CRCU-1. Note that TRANS-MITTER SELECTOR must not be operated too rapidly or no change will occur and the CRCU-1 indication will be erroneous.
- 3.2.3 Connect a pair of high impedance earphones between terminals 1 and 3 of \$204 on CTCU-1 and make sure that the H.T. switches are "ON" and TRANSMITTER SELECTORS set to TX1 on both CRCU-1 and CTCU-1. Check that audio is heard in the phones when the dynamic mike switch is pressed on REMOTE CONTROL and when the carbon mike switch is pressed on LOCAL CONTROL.
- 3.2.4 Repeat the check at terminals 1 and 3 of E205 on CTCU-1 with the TRANSMITTER SELECTORS set to TX2.

## 3.3 Power tests.

3.3.1 Take two healthy TMC GPT-750 transmitters and connect up the system according to CK-10333. Connect up the coaxial relays on the CTCU-1 as shown in CK-10337.

TMC SPECIFICATION NO. S - 10032

COMPILED BY R.W.T. THILE: PRODUCTION TESTING OF SYSTEM CRTC-2, CDTC-1

APPROVED R.W.J.

Take the outputs from the two transmitters to RY301 on CARP-1 and the AMT socket of this relay to a dummy load.

Operate all switches and check for correct transmitter operation and selection, paying special attention to modulation.